

Prepared by {enter your company name here}

Page 2

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

7/5/2016

Time span=0.00-30.00 hrs, dt=0.05 hrs, 601 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Tributary Area to DCB/WQU

Runoff Area=124,850 sf Runoff Depth=0.36"

Flow Length=690' Tc=8.7 min CN=91 Runoff=1.04 cfs 0.086 af

Reach 1R: New Drain

Peak Depth=0.28' Max Vel=4.9 fps Inflow=1.04 cfs 0.086 af

D=15.0" n=0.013 L=13.0' S=0.0200'/' Capacity=9.14 cfs Outflow=1.04 cfs 0.086 af

Reach 2R: New Drain

Peak Depth=0.28' Max Vel=4.9 fps Inflow=1.04 cfs 0.086 af

D=15.0" n=0.013 L=42.0' S=0.0200'/' Capacity=9.14 cfs Outflow=1.03 cfs 0.086 af

Reach 3R: Existing 8" Drain

Peak Depth=0.20' Max Vel=11.4 fps Inflow=1.03 cfs 0.086 af

D=8.0" n=0.013 L=41.0' S=0.1780'/ Capacity=5.10 cfs Outflow=1.03 cfs 0.086 af

Reach DP: DP1

Inflow=1.03 cfs 0.086 af

Outflow=1.03 cfs 0.086 af

Pond 1P: New DCB

Peak Elev=92.35' Storage=0 cf Inflow=1.04 cfs 0.086 af

15.0" x 35.0' Culvert Outflow=1.04 cfs 0.086 af

Total Runoff Area = 2.866 ac Runoff Volume = 0.086 af Average Runoff Depth = 0.36"

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

7/5/2016


Subcatchment 1S: Tributary Area to DCB/WQU

Runoff = 1.04 cfs @ 12.13 hrs, Volume= 0.086 af, Depth= 0.36"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs Type III 24-hr 1 Inch Storm Rainfall=1.00"

_	Α	rea (sf)	CN I	Description		
		92,050		Paved park		
_		32,800	70	Woods, Go	oa, HSG C	
	1	24,850	91	Weighted A	verage	
	Tc (min)	Length (feet)	Slope (ft/ft)		Capacity (cfs)	Description
	4.9	50	0.2000	0.2		Sheet Flow,
	0.2	80	0.2500	8.1		Woods: Light underbrush n= 0.400 P2= 3.20" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
	2.4	375	0.0160	2.6		Shallow Concentrated Flow,
						Paved Kv= 20.3 fps
	1.2	185	0.0160	2.6		Shallow Concentrated Flow,
_						Paved Kv= 20.3 fps
	8.7	690	Total			

Subcatchment 1S: Tributary Area to DCB/WQU



Prepared by {enter your company name here} HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Page 4

7/5/2016

Reach 1R: New Drain

[52] Hint: Inlet conditions not evaluated

[79] Warning: Submerged Pond 1P Primary device # 1 OUTLET by 0.18'

Inflow Area = 2.866 ac, Inflow Depth = 0.36" for 1 Inch Storm event

Inflow = 1.04 cfs @ 12.13 hrs, Volume= 0.086 af


Outflow = 1.04 cfs @ 12.14 hrs, Volume= 0.086 af, Atten= 0%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 4.9 fps, Min. Travel Time= 0.0 min Avg. Velocity = 1.9 fps, Avg. Travel Time= 0.1 min

Peak Depth= 0.28' @ 12.14 hrs Capacity at bank full= 9.14 cfs Inlet Invert= 91.15', Outlet Invert= 90.89' 15.0" Diameter Pipe, n= 0.013 Concrete pipe, bends & connections Length= 13.0' Slope= 0.0200 '/'

Reach 1R: New Drain



Prepared by {enter your company name here}

Page 5

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC 7/5/2016

Reach 2R: New Drain

[52] Hint: Inlet conditions not evaluated

[61] Hint: Submerged 71% of Reach 1R bottom

Inflow Area = 2.866 ac, Inflow Depth = 0.36" for 1 Inch Storm event

Inflow = 1.04 cfs @ 12.14 hrs, Volume= 0.086 af


Outflow = 1.03 cfs @ 12.14 hrs, Volume= 0.086 af, Atten= 0%, Lag= 0.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 4.9 fps, Min. Travel Time= 0.1 min Avg. Velocity = 1.9 fps, Avg. Travel Time= 0.4 min

Peak Depth= 0.28' @ 12.14 hrs Capacity at bank full= 9.14 cfs Inlet Invert= 90.79', Outlet Invert= 89.95' 15.0" Diameter Pipe, n= 0.013 Corrugated PE, smooth interior Length= 42.0' Slope= 0.0200 '/'

Reach 2R: New Drain



Prepared by {enter your company name here}
HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Page 6

7/5/2016

Reach 3R: Existing 8" Drain

[52] Hint: Inlet conditions not evaluated

Inflow Area = 2.866 ac, Inflow Depth = 0.36" for 1 Inch Storm event

Inflow = 1.03 cfs @ 12.14 hrs, Volume= 0.086 af


Outflow = 1.03 cfs @ 12.14 hrs, Volume= 0.086 af, Atten= 0%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 11.4 fps, Min. Travel Time= 0.1 min Avg. Velocity = 4.5 fps, Avg. Travel Time= 0.2 min

Peak Depth= 0.20' @ 12.14 hrs
Capacity at bank full= 5.10 cfs
Inlet Invert= 88.70', Outlet Invert= 81.40'
8.0" Diameter Pipe, n= 0.013 Corrugated PE, smooth interior
Length= 41.0' Slope= 0.1780 '/'

Reach 3R: Existing 8" Drain



Prepared by {enter your company name here} HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC Page 7

7/5/2016

Reach DP: DP1

[40] Hint: Not Described (Outflow=Inflow)


Inflow Area = 2.866 ac, Inflow Depth = 0.36" for 1 Inch Storm event

Inflow = 1.03 cfs @ 12.14 hrs, Volume= 0.086 af

Outflow = 1.03 cfs @ 12.14 hrs, Volume= 0.086 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Reach DP: DP1



Type III 24-hr 1 Inch Storm Rainfall=1.00"

Masiello - Grafton - 88 Westboro Road

Prepared by {enter your company name here}

Page 8

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

7/5/2016

Pond 1P: New DCB

Inflow Area = 2.866 ac, Inflow Depth = 0.36" for 1 Inch Storm event

Inflow = 1.04 cfs @ 12.13 hrs, Volume= 0.086 af

Outflow = 1.04 cfs @ 12.13 hrs, Volume= 0.086 af, Atten= 0%, Lag= 0.0 min

Primary = 1.04 cfs @ 12.13 hrs, Volume= 0.086 af

Routing by Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Peak Elev= 92.35' @ 12.13 hrs Surf.Area= 1 sf Storage= 0 cf

Plug-Flow detention time= 0.0 min calculated for 0.086 af (100% of inflow)

Center-of-Mass det. time= 0.0 min (858.2 - 858.2)


Volume	ln۱	vert Avail.	Storage Sto	orage Description	
#1	91.	80'	9,828 cf Cus	stom Stage Data (Pr	rismatic) Listed below (Recalc)
Elevation (fee		Surf.Area (sq-ft)	Inc.Sto (cubic-fee		
91.8	30	0		0 0	
95.8	30	8	1	16 16	
97.5	50	11,535	9,81	12 9,828	
Device	Routing	Invert	Outlet Device	ces	
#1 Primary 91.80' 15.0" x 35.0' long Culvert CPP, projecting, no headw Outlet Invert= 91.25' S= 0.0157 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior				7 '/' Cc= 0.900	

Primary OutFlow Max=1.02 cfs @ 12.13 hrs HW=92.34' (Free Discharge) 1=Culvert (Inlet Controls 1.02 cfs @ 2.0 fps)

Page 9

7/5/2016

Pond 1P: New DCB



Prepared by {enter your company name here}

Page 10

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

7/5/2016

Time span=0.00-30.00 hrs, dt=0.05 hrs, 601 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Tributary Area to DCB/WQU

Runoff Area=124,850 sf Runoff Depth=1.16"

Flow Length=690' Tc=8.7 min CN=91 Runoff=3.51 cfs 0.278 af

Reach 1R: New Drain

Peak Depth=0.54' Max Vel=6.9 fps Inflow=3.51 cfs 0.278 af

D=15.0" n=0.013 L=13.0' S=0.0200'/' Capacity=9.14 cfs Outflow=3.48 cfs 0.278 af

Reach 2R: New Drain

Peak Depth=0.54' Max Vel=6.9 fps Inflow=3.48 cfs 0.278 af

D=15.0" n=0.013 L=42.0' S=0.0200'/' Capacity=9.14 cfs Outflow=3.47 cfs 0.278 af

Reach 3R: Existing 8" Drain

Peak Depth=0.40' Max Vel=15.7 fps Inflow=3.47 cfs 0.278 af

D=8.0" n=0.013 L=41.0' S=0.1780'/' Capacity=5.10 cfs Outflow=3.47 cfs 0.278 af

Reach DP: DP1

Inflow=3.47 cfs 0.278 af

Outflow=3.47 cfs 0.278 af

Pond 1P: New DCB

Peak Elev=92.98' Storage=1 cf Inflow=3.51 cfs 0.278 af

15.0" x 35.0' Culvert Outflow=3.51 cfs 0.278 af

Total Runoff Area = 2.866 ac Runoff Volume = 0.278 af Average Runoff Depth = 1.16"

Page 11

7/5/2016


Subcatchment 1S: Tributary Area to DCB/WQU

Runoff = 3.51 cfs @ 12.12 hrs, Volume= 0.278 af, Depth= 1.16"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs Type III 24-hr 2 Inch Storm Rainfall=2.00"

_	Α	rea (sf)	CN I	Description		
	92,050 98 Paved parking & roofs 32,800 70 Woods, Good, HSG C					
-		32,800 24,850		Weighted A		
	Tc (min)	Length (feet)	Slope (ft/ft)	•	Capacity (cfs)	Description
_	4.9	50	0.2000	0.2		Sheet Flow,
	0.2	80	0.2500	8.1		Woods: Light underbrush n= 0.400 P2= 3.20" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
	2.4	375	0.0160	2.6		Shallow Concentrated Flow,
_	1.2	185	0.0160	2.6		Paved Kv= 20.3 fps Shallow Concentrated Flow, Paved Kv= 20.3 fps
	8.7	690	Total			

Subcatchment 1S: Tributary Area to DCB/WQU



Prepared by {enter your company name here} HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Page 12

7/5/2016

Reach 1R: New Drain

[52] Hint: Inlet conditions not evaluated

[79] Warning: Submerged Pond 1P Primary device # 1 OUTLET by 0.43'

Inflow Area = 2.866 ac, Inflow Depth = 1.16" for 2 Inch Storm event

Inflow = 3.51 cfs @ 12.12 hrs, Volume= 0.278 af


Outflow = 3.48 cfs @ 12.13 hrs, Volume= 0.278 af, Atten= 1%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 6.9 fps, Min. Travel Time= 0.0 min Avg. Velocity = 2.5 fps, Avg. Travel Time= 0.1 min

Peak Depth= 0.54' @ 12.12 hrs Capacity at bank full= 9.14 cfs Inlet Invert= 91.15', Outlet Invert= 90.89' 15.0" Diameter Pipe, n= 0.013 Concrete pipe, bends & connections Length= 13.0' Slope= 0.0200 '/'

Reach 1R: New Drain



Prepared by {enter your company name here} HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Page 13

7/5/2016

Reach 2R: New Drain

[52] Hint: Inlet conditions not evaluated

[62] Warning: Submerged 14% of Reach 1R inlet

Inflow Area = 2.866 ac, Inflow Depth = 1.16" for 2 Inch Storm event

Inflow = 3.48 cfs @ 12.13 hrs, Volume= 0.278 af


Outflow = 3.47 cfs @ 12.13 hrs, Volume= 0.278 af, Atten= 0%, Lag= 0.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 6.9 fps, Min. Travel Time= 0.1 min Avg. Velocity = 2.5 fps, Avg. Travel Time= 0.3 min

Peak Depth= 0.54' @ 12.13 hrs Capacity at bank full= 9.14 cfs Inlet Invert= 90.79', Outlet Invert= 89.95' 15.0" Diameter Pipe, n= 0.013 Corrugated PE, smooth interior Length= 42.0' Slope= 0.0200 '/'

Reach 2R: New Drain



Prepared by {enter your company name here} HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Page 14

7/5/2016

Reach 3R: Existing 8" Drain

[52] Hint: Inlet conditions not evaluated

Inflow Area = 2.866 ac, Inflow Depth = 1.16" for 2 Inch Storm event

Inflow = 3.47 cfs @ 12.13 hrs, Volume= 0.278 af


Outflow = 3.47 cfs @ 12.13 hrs, Volume= 0.278 af, Atten= 0%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 15.7 fps, Min. Travel Time= 0.0 min Avg. Velocity = 5.9 fps, Avg. Travel Time= 0.1 min

Peak Depth= 0.40' @ 12.13 hrs
Capacity at bank full= 5.10 cfs
Inlet Invert= 88.70', Outlet Invert= 81.40'
8.0" Diameter Pipe, n= 0.013 Corrugated PE, smooth interior
Length= 41.0' Slope= 0.1780 '/'

Reach 3R: Existing 8" Drain



Prepared by {enter your company name here} HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC Page 15

7/5/2016

Reach DP: DP1

[40] Hint: Not Described (Outflow=Inflow)


Inflow Area = 2.866 ac, Inflow Depth = 1.16" for 2 Inch Storm event

Inflow = 3.47 cfs @ 12.13 hrs, Volume= 0.278 af

Outflow = 3.47 cfs @ 12.13 hrs, Volume= 0.278 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Reach DP: DP1



Type III 24-hr 2 Inch Storm Rainfall=2.00"

Prepared by {enter your company name here}

Page 16

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

7/5/2016

Pond 1P: New DCB

Inflow Area = 2.866 ac, Inflow Depth = 1.16" for 2 Inch Storm event

Inflow = 3.51 cfs @ 12.12 hrs, Volume= 0.278 af

Outflow = 3.51 cfs @ 12.12 hrs, Volume= 0.278 af, Atten= 0%, Lag= 0.0 min

Primary = 3.51 cfs @ 12.12 hrs, Volume= 0.278 af

Routing by Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Peak Elev= 92.98' @ 12.12 hrs Surf.Area= 2 sf Storage= 1 cf

Plug-Flow detention time= 0.0 min calculated for 0.277 af (100% of inflow)


Center-of-Mass det. time= 0.0 min (823.8 - 823.8)

Volume	ln۷	vert Avail.	.Storage	Storage	e Description			
#1	91.	80'	9,828 cf	Custom Stage Data (Prismatic) Listed below (Recalc)				
Elevation (fee		Surf.Area (sq-ft)	Inc. (cubic	Store -feet)	Cum.Store (cubic-feet)			
91.8	30	0	0		0			
95.8	30	8		16	16			
97.5	50	11,535	(9,812	9,828			
Device	Routing	Invert	Outlet Devices					
#1 Primary 91.80'		Outlet In	15.0" x 35.0' long Culvert CPP, projecting, no headwall, Ke= 0.900 Outlet Invert= 91.25' S= 0.0157 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior					

Primary OutFlow Max=3.42 cfs @ 12.12 hrs HW=92.95' (Free Discharge) 1=Culvert (Inlet Controls 3.42 cfs @ 2.9 fps)

Page 17 7/5/2016

Pond 1P: New DCB



Page 18

7/5/2016

Time span=0.00-30.00 hrs, dt=0.05 hrs, 601 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Tributary Area to DCB/WQU

Runoff Area=124,850 sf Runoff Depth=2.26"

Flow Length=690' Tc=8.7 min CN=91 Runoff=6.72 cfs 0.539 af

Reach 1R: New Drain

Peak Depth=0.80' Max Vel=8.1 fps Inflow=6.71 cfs 0.539 af

D=15.0" n=0.013 L=13.0' S=0.0200'/' Capacity=9.14 cfs Outflow=6.70 cfs 0.539 af

Reach 2R: New Drain

Peak Depth=0.79' Max Vel=8.1 fps Inflow=6.70 cfs 0.539 af

D=15.0" n=0.013 L=42.0' S=0.0200'/' Capacity=9.14 cfs Outflow=6.64 cfs 0.539 af

Reach 3R: Existing 8" Drain

Peak Depth=0.67' Max Vel=16.7 fps Inflow=6.64 cfs 0.539 af

D=8.0" n=0.013 L=41.0' S=0.1780'/' Capacity=5.10 cfs Outflow=5.10 cfs 0.539 af

Reach DP: DP1

Inflow=5.10 cfs 0.539 af

Outflow=5.10 cfs 0.539 af

Pond 1P: New DCB

Peak Elev=94.48' Storage=7 cf Inflow=6.72 cfs 0.539 af

15.0" x 35.0' Culvert Outflow=6.71 cfs 0.539 af

Total Runoff Area = 2.866 ac Runoff Volume = 0.539 af Average Runoff Depth = 2.26"

Page 19

7/5/2016


Subcatchment 1S: Tributary Area to DCB/WQU

Runoff = 6.72 cfs @ 12.12 hrs, Volume= 0.539 af, Depth= 2.26"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs Type III 24-hr 2-year storm Rainfall=3.20"

_	Α	rea (sf)	CN I	Description		
	92,050 98 Paved parking & roofs 32,800 70 Woods, Good, HSG C					
-		32,800 24,850		Weighted A		
	Tc (min)	Length (feet)	Slope (ft/ft)	•	Capacity (cfs)	Description
_	4.9	50	0.2000	0.2		Sheet Flow,
	0.2	80	0.2500	8.1		Woods: Light underbrush n= 0.400 P2= 3.20" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
	2.4	375	0.0160	2.6		Shallow Concentrated Flow,
_	1.2	185	0.0160	2.6		Paved Kv= 20.3 fps Shallow Concentrated Flow, Paved Kv= 20.3 fps
	8.7	690	Total			

Subcatchment 1S: Tributary Area to DCB/WQU



Prepared by {enter your company name here}
HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Page 20

7/5/2016

Reach 1R: New Drain

[52] Hint: Inlet conditions not evaluated

[79] Warning: Submerged Pond 1P Primary device # 1 INLET by 0.13'

Inflow Area = 2.866 ac, Inflow Depth = 2.26" for 2-year storm event

Inflow = 6.71 cfs @ 12.12 hrs, Volume= 0.539 af


Outflow = 6.70 cfs @ 12.12 hrs, Volume= 0.539 af, Atten= 0%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 8.1 fps, Min. Travel Time= 0.0 min Avg. Velocity = 2.9 fps, Avg. Travel Time= 0.1 min

Peak Depth= 0.80' @ 12.12 hrs Capacity at bank full= 9.14 cfs Inlet Invert= 91.15', Outlet Invert= 90.89' 15.0" Diameter Pipe, n= 0.013 Concrete pipe, bends & connections Length= 13.0' Slope= 0.0200 '/'

Reach 1R: New Drain



Prepared by {enter your company name here}
HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Page 21

7/5/2016

Reach 2R: New Drain

[52] Hint: Inlet conditions not evaluated

[62] Warning: Submerged 34% of Reach 1R inlet

Inflow Area = 2.866 ac, Inflow Depth = 2.26" for 2-year storm event

Inflow = 6.70 cfs @ 12.12 hrs, Volume= 0.539 af


Outflow = 6.64 cfs @ 12.13 hrs, Volume= 0.539 af, Atten= 1%, Lag= 0.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 8.1 fps, Min. Travel Time= 0.1 min Avg. Velocity = 2.9 fps, Avg. Travel Time= 0.2 min

Peak Depth= 0.79' @ 12.12 hrs Capacity at bank full= 9.14 cfs Inlet Invert= 90.79', Outlet Invert= 89.95' 15.0" Diameter Pipe, n= 0.013 Corrugated PE, smooth interior Length= 42.0' Slope= 0.0200 '/'

Reach 2R: New Drain



Prepared by {enter your company name here} HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC Page 22

7/5/2016

Reach 3R: Existing 8" Drain

[52] Hint: Inlet conditions not evaluated

[55] Hint: Peak inflow is 130% of Manning's capacity

[76] Warning: Detained 0.013 af (Pond w/culvert advised)

Inflow Area = 2.866 ac, Inflow Depth = 2.26" for 2-year storm event

Inflow = 6.64 cfs @ 12.13 hrs, Volume= 0.539 af


Outflow = 5.10 cfs @ 12.15 hrs, Volume= 0.539 af, Atten= 23%, Lag= 1.4 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 16.7 fps, Min. Travel Time= 0.0 min Avg. Velocity = 6.8 fps, Avg. Travel Time= 0.1 min

Peak Depth= 0.67' @ 12.10 hrs
Capacity at bank full= 5.10 cfs
Inlet Invert= 88.70', Outlet Invert= 81.40'
8.0" Diameter Pipe, n= 0.013 Corrugated PE, smooth interior
Length= 41.0' Slope= 0.1780 '/'

Reach 3R: Existing 8" Drain



Prepared by {enter your company name here} HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC Page 23

7/5/2016

Reach DP: DP1

[40] Hint: Not Described (Outflow=Inflow)


Inflow Area = 2.866 ac, Inflow Depth = 2.26" for 2-year storm event

Inflow = 5.10 cfs @ 12.15 hrs, Volume= 0.539 af

Outflow = 5.10 cfs @ 12.15 hrs, Volume= 0.539 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Reach DP: DP1



Type III 24-hr 2-year storm Rainfall=3.20"

Prepared by {enter your company name here}

Page 24

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

7/5/2016

Pond 1P: New DCB

Inflow Area = 2.866 ac, Inflow Depth = 2.26" for 2-year storm event

Inflow = 6.72 cfs @ 12.12 hrs, Volume= 0.539 af

Outflow = 6.71 cfs @ 12.12 hrs, Volume= 0.539 af, Atten= 0%, Lag= 0.1 min

Primary = 6.71 cfs @ 12.12 hrs, Volume= 0.539 af

Routing by Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs Peak Elev= 94.48' @ 12.12 hrs Surf.Area= 5 sf Storage= 7 cf


Plug-Flow detention time= (not calculated: outflow precedes inflow) Center-of-Mass det. time= 0.0 min (805.0 - 805.0)

Volume	Inv	vert Avai	.Storage	Storage	e Description			
#1	91.	.80'	9,828 cf	Custon	Custom Stage Data (Prismatic) Listed below (Recalc)			
Elevation	on	Surf.Area	Inc	.Store	Cum.Store			
(fee	et)	(sq-ft)	(cubic-feet)		(cubic-feet)			
91.8	30	0		0	0			
95.8	30	8		16	16			
97.5	50	11,535		9,812	9,828			
Device Routi		Invert	Outlet D	Devices				
#1 Primary		91.80' 15.0" x Outlet li		x 35.0' long Culvert CPP, projecting, no headwall, Ke= 0.900 nvert= 91.25' S= 0.0157 '/' Cc= 0.900 3 Corrugated PE, smooth interior				

Primary OutFlow Max=6.53 cfs @ 12.12 hrs HW=94.38' (Free Discharge) 1=Culvert (Inlet Controls 6.53 cfs @ 5.3 fps)

Page 25 7/5/2016

Pond 1P: New DCB





Prepared by {enter your company name here}

Page 26

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

7/5/2016

Time span=0.00-30.00 hrs, dt=0.05 hrs, 601 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Tributary Area to DCB/WQU

Runoff Area=124,850 sf Runoff Depth=3.79"

Flow Length=690' Tc=8.7 min CN=91 Runoff=11.01 cfs 0.905 af

Reach 1R: New Drain

Peak Depth=1.02' Max Vel=8.5 fps Inflow=9.08 cfs 0.907 af

D=15.0" n=0.013 L=13.0' S=0.0200'/' Capacity=9.14 cfs Outflow=9.10 cfs 0.907 af

Reach 2R: New Drain

Peak Depth=1.02' Max Vel=8.5 fps Inflow=9.10 cfs 0.907 af

D=15.0" n=0.013 L=42.0' S=0.0200'/' Capacity=9.14 cfs Outflow=9.13 cfs 0.907 af

Reach 3R: Existing 8" Drain

Peak Depth=0.67' Max Vel=16.6 fps Inflow=9.13 cfs 0.907 af

D=8.0" n=0.013 L=41.0' S=0.1780'/' Capacity=5.10 cfs Outflow=5.10 cfs 0.907 af

Reach DP: DP1

Inflow=5.10 cfs 0.907 af

Outflow=5.10 cfs 0.907 af

Pond 1P: New DCB

Peak Elev=96.22' Storage=609 cf Inflow=11.01 cfs 0.905 af

15.0" x 35.0' Culvert Outflow=9.08 cfs 0.907 af

Total Runoff Area = 2.866 ac Runoff Volume = 0.905 af Average Runoff Depth = 3.79"

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC


Subcatchment 1S: Tributary Area to DCB/WQU

Runoff = 11.01 cfs @ 12.12 hrs, Volume= 0.905 af, Depth= 3.79"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs Type III 24-hr 10-year storm Rainfall=4.80"

_	Α	rea (sf)	CN I	Description		
		92,050		Paved park		
_		32,800	70	Woods, Go	oa, HSG C	
	1	24,850	91	Weighted A	verage	
	Tc (min)	Length (feet)	Slope (ft/ft)		Capacity (cfs)	Description
	4.9	50	0.2000	0.2		Sheet Flow,
	0.2	80	0.2500	8.1		Woods: Light underbrush n= 0.400 P2= 3.20" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
	2.4	375	0.0160	2.6		Shallow Concentrated Flow,
						Paved Kv= 20.3 fps
	1.2	185	0.0160	2.6		Shallow Concentrated Flow,
_						Paved Kv= 20.3 fps
	8.7	690	Total			

Subcatchment 1S: Tributary Area to DCB/WQU



Page 28 7/5/2016

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Reach 1R: New Drain

[52] Hint: Inlet conditions not evaluated

[88] Warning: Qout>Qin may require Finer Routing>1

[79] Warning: Submerged Pond 1P Primary device # 1 INLET by 0.37'

Inflow Area = 2.866 ac, Inflow Depth = 3.80" for 10-year storm event

Inflow = 9.08 cfs @ 12.19 hrs, Volume= 0.907 af


Outflow = 9.10 cfs @ 12.19 hrs, Volume= 0.907 af, Atten= 0%, Lag= 0.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 8.5 fps, Min. Travel Time= 0.0 min Avg. Velocity = 3.3 fps, Avg. Travel Time= 0.1 min

Peak Depth= 1.02' @ 12.19 hrs
Capacity at bank full= 9.14 cfs
Inlet Invert= 91.15', Outlet Invert= 90.89'
15.0" Diameter Pipe, n= 0.013 Concrete pipe, bends & connections
Length= 13.0' Slope= 0.0200 '/'

Reach 1R: New Drain



Prepared by {enter your company name here}

Page 29 7/5/2016

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Reach 2R: New Drain

[52] Hint: Inlet conditions not evaluated

[88] Warning: Qout>Qin may require Finer Routing>1

[62] Warning: Submerged 53% of Reach 1R inlet

Inflow Area = 2.866 ac, Inflow Depth = 3.80" for 10-year storm event

Inflow = 9.10 cfs @ 12.19 hrs, Volume= 0.907 af


Outflow = 9.13 cfs @ 12.20 hrs, Volume= 0.907 af, Atten= 0%, Lag= 0.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 8.5 fps, Min. Travel Time= 0.1 min Avg. Velocity = 3.3 fps, Avg. Travel Time= 0.2 min

Peak Depth= 1.02' @ 12.20 hrs
Capacity at bank full= 9.14 cfs
Inlet Invert= 90.79', Outlet Invert= 89.95'
15.0" Diameter Pipe, n= 0.013 Corrugated PE, smooth interior
Length= 42.0' Slope= 0.0200 '/'

Reach 2R: New Drain



Page 30

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

7/5/2016

Reach 3R: Existing 8" Drain

[52] Hint: Inlet conditions not evaluated

[55] Hint: Peak inflow is 179% of Manning's capacity

[76] Warning: Detained 0.092 af (Pond w/culvert advised)

Inflow Area = 2.866 ac, Inflow Depth = 3.80" for 10-year storm event

Inflow = 9.13 cfs @ 12.20 hrs, Volume= 0.907 af


Outflow = 5.10 cfs @ 12.05 hrs, Volume= 0.907 af, Atten= 44%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 16.6 fps, Min. Travel Time= 0.0 min Avg. Velocity = 7.7 fps, Avg. Travel Time= 0.1 min

Peak Depth= 0.67' @ 12.00 hrs
Capacity at bank full= 5.10 cfs
Inlet Invert= 88.70', Outlet Invert= 81.40'
8.0" Diameter Pipe, n= 0.013 Corrugated PE, smooth interior
Length= 41.0' Slope= 0.1780 '/'

Reach 3R: Existing 8" Drain



Page 31

7/5/2016

Reach DP: DP1

[40] Hint: Not Described (Outflow=Inflow)


Inflow Area = 2.866 ac, Inflow Depth = 3.80" for 10-year storm event

Inflow = 5.10 cfs @ 12.05 hrs, Volume= 0.907 af

Outflow = 5.10 cfs @ 12.05 hrs, Volume= 0.907 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Reach DP: DP1



Prepared by {enter your company name here}

Page 32

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

7/5/2016

Pond 1P: New DCB

[85] Warning: Oscillations may require Finer Routing>1

Inflow Area = 2.866 ac, Inflow Depth = 3.79" for 10-year storm event

Inflow = 11.01 cfs @ 12.12 hrs, Volume= 0.905 af

Outflow = 9.08 cfs @ 12.19 hrs, Volume= 0.907 af, Atten= 17%, Lag= 4.1 min

Primary = 9.08 cfs @ 12.19 hrs, Volume= 0.907 af

Routing by Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs Peak Elev= 96.22' @ 12.19 hrs Surf.Area= 2,836 sf Storage= 609 cf Plug-Flow detention time= (not calculated: outflow precedes inflow)


Center-of-Mass det. time= 0.4 min (791.1 - 790.7)

Volume	In	vert Avail.	Storage Stora	ge Description		
#1	91	.80'	9,828 cf Cust	Custom Stage Data (Prismatic) Listed below (Recalc)		
Elevation (feet) 91.80 95.80 97.50		Surf.Area (sq-ft) 0 8 11,535	Inc.Store (cubic-feet) 0 16 9,812	(cubic-feet) 0 16		
Device	Routing	lnvert	Outlet Device	S		
#1 Primary 91.80'		15.0" x 35.0' long Culvert CPP, projecting, no headwall, Ke= 0.900 Outlet Invert= 91.25' S= 0.0157 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior				

Primary OutFlow Max=9.07 cfs @ 12.19 hrs HW=96.21' (Free Discharge) 1=Culvert (Inlet Controls 9.07 cfs @ 7.4 fps)

Page 33 7/5/2016

Pond 1P: New DCB





Page 34

7/5/2016

Time span=0.00-30.00 hrs, dt=0.05 hrs, 601 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Tributary Area to DCB/WQU

Runoff Area=124,850 sf Runoff Depth=4.47"

Flow Length=690' Tc=8.7 min CN=91 Runoff=12.87 cfs 1.067 af

Reach 1R: New Drain

Peak Depth=1.06' Max Vel=8.5 fps Inflow=9.37 cfs 1.071 af

D=15.0" n=0.013 L=13.0' S=0.0200'/' Capacity=9.14 cfs Outflow=9.38 cfs 1.071 af

Reach 2R: New Drain

Peak Depth=1.06' Max Vel=8.5 fps Inflow=9.38 cfs 1.071 af

D=15.0" n=0.013 L=42.0' S=0.0200'/' Capacity=9.14 cfs Outflow=9.39 cfs 1.071 af

Reach 3R: Existing 8" Drain

Peak Depth=0.67' Max Vel=16.6 fps Inflow=9.39 cfs 1.071 af

D=8.0" n=0.013 L=41.0' S=0.1780 '/' Capacity=5.10 cfs Outflow=5.10 cfs 1.071 af

Reach DP: DP1

Inflow=5.10 cfs 1.071 af Outflow=5.10 cfs 1.071 af

Pond 1P: New DCB

Peak Elev=96.46' Storage=1,513 cf Inflow=12.87 cfs 1.067 af

15.0" x 35.0' Culvert Outflow=9.37 cfs 1.071 af

Total Runoff Area = 2.866 ac Runoff Volume = 1.067 af Average Runoff Depth = 4.47"

Page 35

7/5/2016


Subcatchment 1S: Tributary Area to DCB/WQU

Runoff = 12.87 cfs @ 12.12 hrs, Volume= 1.067 af, Depth= 4.47"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs Type III 24-hr 25-year storm Rainfall=5.50"

_	Α	rea (sf)	CN I	Description		
	92,050 98 Paved parking & roofs 32,800 70 Woods, Good, HSG C					
-		32,800 24,850		Weighted A		
	Tc (min)	Length (feet)	Slope (ft/ft)	•	Capacity (cfs)	Description
_	4.9	50	0.2000	0.2		Sheet Flow,
	0.2	80	0.2500	8.1		Woods: Light underbrush n= 0.400 P2= 3.20" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
	2.4	375	0.0160	2.6		Shallow Concentrated Flow,
_	1.2	185	0.0160	2.6		Paved Kv= 20.3 fps Shallow Concentrated Flow, Paved Kv= 20.3 fps
	8.7	690	Total			

Subcatchment 1S: Tributary Area to DCB/WQU



HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Reach 1R: New Drain

[52] Hint: Inlet conditions not evaluated

[55] Hint: Peak inflow is 103% of Manning's capacity

[88] Warning: Qout>Qin may require Finer Routing>1

[79] Warning: Submerged Pond 1P Primary device # 1 INLET by 0.41'

Inflow Area = 2.866 ac, Inflow Depth = 4.48" for 25-year storm event

Inflow = 9.37 cfs @ 12.22 hrs, Volume= 1.071 af


Outflow = 9.38 cfs @ 12.21 hrs, Volume= 1.071 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 8.5 fps, Min. Travel Time= 0.0 min Avg. Velocity = 3.5 fps, Avg. Travel Time= 0.1 min

Peak Depth= 1.06' @ 12.21 hrs
Capacity at bank full= 9.14 cfs
Inlet Invert= 91.15', Outlet Invert= 90.89'
15.0" Diameter Pipe, n= 0.013 Concrete pipe, bends & connections
Length= 13.0' Slope= 0.0200 '/'

Reach 1R: New Drain



Prepared by {enter your company name here}

Page 37 7/5/2016

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Reach 2R: New Drain

[52] Hint: Inlet conditions not evaluated

[55] Hint: Peak inflow is 103% of Manning's capacity

[88] Warning: Qout>Qin may require Finer Routing>1

[62] Warning: Submerged 56% of Reach 1R inlet

Inflow Area = 2.866 ac, Inflow Depth = 4.48" for 25-year storm event

Inflow = 9.38 cfs @ 12.21 hrs, Volume= 1.071 af


Outflow = 9.39 cfs @ 12.21 hrs, Volume= 1.071 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 8.5 fps, Min. Travel Time= 0.1 min Avg. Velocity = 3.5 fps, Avg. Travel Time= 0.2 min

Peak Depth= 1.06' @ 12.21 hrs
Capacity at bank full= 9.14 cfs
Inlet Invert= 90.79', Outlet Invert= 89.95'
15.0" Diameter Pipe, n= 0.013 Corrugated PE, smooth interior
Length= 42.0' Slope= 0.0200 '/'

Reach 2R: New Drain



Page 38

7/5/2016

Reach 3R: Existing 8" Drain

[52] Hint: Inlet conditions not evaluated

[55] Hint: Peak inflow is 184% of Manning's capacity

[76] Warning: Detained 0.138 af (Pond w/culvert advised)

Inflow Area = 2.866 ac, Inflow Depth = 4.48" for 25-year storm event

Inflow = 9.39 cfs @ 12.21 hrs, Volume= 1.071 af


Outflow = 5.10 cfs @ 12.00 hrs, Volume= 1.071 af, Atten= 46%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 16.6 fps, Min. Travel Time= 0.0 min Avg. Velocity = 8.0 fps, Avg. Travel Time= 0.1 min

Peak Depth= 0.67' @ 11.95 hrs
Capacity at bank full= 5.10 cfs
Inlet Invert= 88.70', Outlet Invert= 81.40'
8.0" Diameter Pipe, n= 0.013 Corrugated PE, smooth interior
Length= 41.0' Slope= 0.1780 '/'

Reach 3R: Existing 8" Drain



Page 39

7/5/2016

Reach DP: DP1

[40] Hint: Not Described (Outflow=Inflow)


Inflow Area = 2.866 ac, Inflow Depth = 4.48" for 25-year storm event

Inflow = 5.10 cfs @ 12.00 hrs, Volume= 1.071 af

Outflow = 5.10 cfs @ 12.00 hrs, Volume= 1.071 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Reach DP: DP1



Prepared by {enter your company name here}

Page 40

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

7/5/2016

Pond 1P: New DCB

[85] Warning: Oscillations may require Finer Routing>1

Inflow Area = 2.866 ac, Inflow Depth = 4.47" for 25-year storm event

Inflow = 12.87 cfs @ 12.12 hrs, Volume= 1.067 af

Outflow = 9.37 cfs @ 12.22 hrs, Volume= 1.071 af, Atten= 27%, Lag= 5.9 min

Primary = 9.37 cfs @ 12.22 hrs, Volume= 1.071 af

Routing by Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs Peak Elev= 96.46' @ 12.22 hrs Surf.Area= 4,506 sf Storage= 1,513 cf Plug-Flow detention time= (not calculated: outflow precedes inflow)


Center-of-Mass det. time= 0.6 min (786.9 - 786.3)

Volume	In	vert Avail.	Storage Sto	orage	Description	
#1	91	.80'	9,828 cf C u	ıstom	Stage Data (Pri	ismatic) Listed below (Recalc)
Elevatio	et)	Surf.Area (sq-ft)	Inc.Sto (cubic-fe	et)	Cum.Store (cubic-feet)	
91.8	_	0		0	0	
95.8 97.5		8 11,535	9,8	16 12	16 9,828	
Device	Routing	lnvert	Outlet Devi	ces		
#1 Primary 91.80' 15.0" x 35.0' long Culvert CPP, projecting, no headwall, Ke= 0.900 Outlet Invert= 91.25' S= 0.0157'/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior					'/' Cc= 0.900	

Primary OutFlow Max=9.36 cfs @ 12.22 hrs HW=96.45' (Free Discharge) 1=Culvert (Inlet Controls 9.36 cfs @ 7.6 fps)

Page 41 7/5/2016

Pond 1P: New DCB



Page 42

7/5/2016

Time span=0.00-30.00 hrs, dt=0.05 hrs, 601 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Tributary Area to DCB/WQU

Runoff Area=124,850 sf Runoff Depth=5.84"

Flow Length=690' Tc=8.7 min CN=91 Runoff=16.57 cfs 1.395 af

Reach 1R: New Drain

Peak Depth=1.17' Max Vel=8.5 fps Inflow=9.82 cfs 1.395 af

D=15.0" n=0.013 L=13.0' S=0.0200'/' Capacity=9.14 cfs Outflow=9.83 cfs 1.395 af

Reach 2R: New Drain

Peak Depth=1.25' Max Vel=8.5 fps Inflow=9.83 cfs 1.395 af

D=15.0" n=0.013 L=42.0' S=0.0200'/' Capacity=9.14 cfs Outflow=9.77 cfs 1.395 af

Reach 3R: Existing 8" Drain

Peak Depth=0.67' Max Vel=16.6 fps Inflow=9.77 cfs 1.395 af

D=8.0" n=0.013 L=41.0' S=0.1780'/' Capacity=5.10 cfs Outflow=5.10 cfs 1.395 af

Reach DP: DP1

Inflow=5.10 cfs 1.395 af

Outflow=5.10 cfs 1.395 af

Pond 1P: New DCB

Peak Elev=96.86' Storage=3,802 cf Inflow=16.57 cfs 1.395 af

15.0" x 35.0' Culvert Outflow=9.82 cfs 1.395 af

Total Runoff Area = 2.866 ac Runoff Volume = 1.395 af Average Runoff Depth = 5.84"

7/5/2016


Subcatchment 1S: Tributary Area to DCB/WQU

Runoff = 16.57 cfs @ 12.12 hrs, Volume= 1.395 af, Depth= 5.84"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs Type III 24-hr 100-year storm Rainfall=6.90"

_	Α	rea (sf)	CN I	Description		
		92,050		Paved park Woods, Go		
-		32,800 24,850		Weighted A		
	Tc (min)	Length (feet)	Slope (ft/ft)	•	Capacity (cfs)	Description
_	4.9	50	0.2000	0.2		Sheet Flow,
	0.2	80	0.2500	8.1		Woods: Light underbrush n= 0.400 P2= 3.20" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
	2.4	375	0.0160	2.6		Shallow Concentrated Flow,
_	1.2	185	0.0160	2.6		Paved Kv= 20.3 fps Shallow Concentrated Flow, Paved Kv= 20.3 fps
	8.7	690	Total			

Subcatchment 1S: Tributary Area to DCB/WQU



Prepared by {enter your company name here}
HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Page 44

7/5/2016

Reach 1R: New Drain

[52] Hint: Inlet conditions not evaluated

[55] Hint: Peak inflow is 107% of Manning's capacity

[88] Warning: Qout>Qin may require Finer Routing>1

[79] Warning: Submerged Pond 1P Primary device # 1 INLET by 0.52'

Inflow Area = 2.866 ac, Inflow Depth = 5.84" for 100-year storm event

Inflow = 9.82 cfs @ 12.27 hrs, Volume= 1.395 af


Outflow = 9.83 cfs @ 12.26 hrs, Volume= 1.395 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 8.5 fps, Min. Travel Time= 0.0 min Avg. Velocity = 3.7 fps, Avg. Travel Time= 0.1 min

Peak Depth= 1.17' @ 12.26 hrs Capacity at bank full= 9.14 cfs Inlet Invert= 91.15', Outlet Invert= 90.89' 15.0" Diameter Pipe, n= 0.013 Concrete pipe, bends & connections Length= 13.0' Slope= 0.0200 '/'

Reach 1R: New Drain



Prepared by {enter your company name here}

Page 45 7/5/2016

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Reach 2R: New Drain

[52] Hint: Inlet conditions not evaluated

[55] Hint: Peak inflow is 108% of Manning's capacity

[76] Warning: Detained 0.013 af (Pond w/culvert advised)

[62] Warning: Submerged 71% of Reach 1R inlet

Inflow Area = 2.866 ac, Inflow Depth = 5.84" for 100-year storm event

Inflow = 9.83 cfs @ 12.26 hrs, Volume= 1.395 af


Outflow = 9.77 cfs @ 12.18 hrs, Volume= 1.395 af, Atten= 1%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 8.5 fps, Min. Travel Time= 0.1 min Avg. Velocity = 3.7 fps, Avg. Travel Time= 0.2 min

Peak Depth= 1.25' @ 12.25 hrs Capacity at bank full= 9.14 cfs Inlet Invert= 90.79', Outlet Invert= 89.95' 15.0" Diameter Pipe, n= 0.013 Corrugated PE, smooth interior Length= 42.0' Slope= 0.0200 '/'

Reach 2R: New Drain



Prepared by {enter your company name here}
HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

Page 46

7/5/2016

Reach 3R: Existing 8" Drain

[52] Hint: Inlet conditions not evaluated

[55] Hint: Peak inflow is 192% of Manning's capacity

[76] Warning: Detained 0.226 af (Pond w/culvert advised)

Inflow Area = 2.866 ac, Inflow Depth = 5.84" for 100-year storm event

Inflow = 9.77 cfs @ 12.18 hrs, Volume= 1.395 af


Outflow = 5.10 cfs @ 11.90 hrs, Volume= 1.395 af, Atten= 48%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Max. Velocity= 16.6 fps, Min. Travel Time= 0.0 min Avg. Velocity = 8.6 fps, Avg. Travel Time= 0.1 min

Peak Depth= 0.67' @ 11.85 hrs
Capacity at bank full= 5.10 cfs
Inlet Invert= 88.70', Outlet Invert= 81.40'
8.0" Diameter Pipe, n= 0.013 Corrugated PE, smooth interior
Length= 41.0' Slope= 0.1780 '/'

Reach 3R: Existing 8" Drain



Page 47

7/5/2016

Reach DP: DP1

[40] Hint: Not Described (Outflow=Inflow)


Inflow Area = 2.866 ac, Inflow Depth = 5.84" for 100-year storm event

Inflow = 5.10 cfs @ 11.90 hrs, Volume= 1.395 af

Outflow = 5.10 cfs @ 11.90 hrs, Volume= 1.395 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs

Reach DP: DP1



Type III 24-hr 100-year storm Rainfall=6.90"

Prepared by {enter your company name here}

Page 48

HydroCAD® 7.10 s/n 000655 © 2005 HydroCAD Software Solutions LLC

7/5/2016

Pond 1P: New DCB

[85] Warning: Oscillations may require Finer Routing>1

Inflow Area = 2.866 ac, Inflow Depth = 5.84" for 100-year storm event

Inflow = 16.57 cfs @ 12.12 hrs, Volume= 1.395 af

Outflow = 9.82 cfs @ 12.27 hrs, Volume= 1.395 af, Atten= 41%, Lag= 8.8 min

Primary = 9.82 cfs @ 12.27 hrs, Volume= 1.395 af

Routing by Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.05 hrs Peak Elev= 96.86' @ 12.27 hrs Surf.Area= 7,165 sf Storage= 3,802 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 1.4 min (780.7 - 779.3)

Volume	In	vert Avail.	Storage Stora	age Description		
#1	91	.80'	9,828 cf Cust	Custom Stage Data (Prismatic) Listed below (Recalc)		
Elevation (feet) 91.80 95.80 97.50		Surf.Area (sq-ft) 0 8 11,535	Inc.Store (cubic-feet) 0 16 9,812	(cubic-feet) 0 0 5 16		
Device	Routing	lnvert	Outlet Device	es		
#1	#1 Primary 91.80' 15.0" x 35.0' long Culvert CPP, projecting, no headwall, Ke= 0.900 Outlet Invert= 91.25' S= 0.0157 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior					

Primary OutFlow Max=9.81 cfs @ 12.27 hrs HW=96.85' (Free Discharge) 1=Culvert (Inlet Controls 9.81 cfs @ 8.0 fps)

Page 49 7/5/2016

Pond 1P: New DCB

